

# THE HYDERABAD CRICKET ASSOCIATION

Rajiv Gandhi International Cricket Stadium, Uppal, Hyderabad.

## ATTACHMENT – 04

### **BILL OF QUANTITIES & PRICE QUOTE**

**SUB:-** Supply and Laying of Tiles for Flooring and Toilet Walls at Gymkhana Ground Secunderabad.

S. No	Description of item	QTY	Unit	Rate @ Unit	Amount (Rs.)
1	Dismantling the old flooring tiles and wall tiles in toilets, door frames, doors, toilet windows and granite platform in players dress room and dispose of the debris to outside of the ground. Including cost and conveyance of all materials and labour charges for dismantle etc complete for finished item of work.	2500.00	Sft		
2	Flooring with Anti skid floor tiles of 1st quality and make as approved by Engineer-in-charge of size 600 x 600 mm ( Khajaria / Somani / Jhonson), 8mm thickness regular finish and normal colours with borders and design as per the approved flooring pattern as directed by the Engineer-In -Charge set over a base coat of CM (1:8) prop. 12mm thick over CC bed already laid including neat cement slurry of honey like consistancy and jointed neatly with white cement paste to full depth mixed with pigment of matching shade including cost and conveyance of all materials like cement, sand, water, tiles, white cement etc., to site (excluding cost of C.C. bed) cost of base coat and all labour charges for mixing of cement mortar, laying tiles to required slope as directed by the Engineer- in-charge etc., complete for finished item of work.	600.00	Sft		
3	Supply and cladding of glazed wall tiles of required size and approved brands like ( Khajaria / Somani / Jhonson) and normal colours. including cost and conveyance of all materials like cement, sand, water, tiles, white cement etc., to site (excluding cost of C.C. bed) cost of base coat and all labour charges for mixing of cement mortar, cladding of tiles to walls etc., complete for finished item of work.	1600.00	Sft		


4	Supply and fixing of 18mm thick granite of approved colour for wash basin basin counter top with full moulding front and sides and vertical supports with double granite cladding and moulding front side of verticals. Including cost and conveyance of all materials and labour charges for fixing and cutting of granite for fixing of wash basins etc complete for finished item of work.	2200.00	Sft		
5	Supply and fixing of granite frames for wash room entrance door areas. Including cost and conveyance of all materials and labour charges for fixing and cutting of granite to required sizes to fix to door frames etc, complete for finished item of work.	272.00	Sft		
Net Amount					
Add GST @ _____ %					
<b>Total Amount</b>					

(Rupees in words \_\_\_\_\_ only)

**Note:-**

- The quoted price is inclusive of all materials, labour, equipment, tools & plants, scaffolding, transportation, insurance, taxes, duties, testing, finishing, and all incidental charges, with no extra claim whatsoever.
- Acceptance of any tender is subject to negotiations and HCA reserves it's right to negotiate with any tenderer including the lowest.


**SIGNATURE OF APPLICANT**

**NAME:** \_\_\_\_\_

**DESIGNATION:** \_\_\_\_\_

**FIRM/COMPANY:** \_\_\_\_\_

**DATE:** \_\_\_\_\_

  
**(IMTIAZ KHAN)**  
**Chief Executive Officer**

