

THE HYDERABAD CRICKET ASSOCIATION

Rajiv Gandhi International Cricket Stadium, Uppal, Hyderabad.

ATTACHMENT – 09

BILL OF QUANTITIES & PRICE QUOTE

SUB:- Providing Plastering and CC bed for under Flooring of Tiles in Toilets and Dismantle the existing tiles and doors at Gymkhana Ground Secunderabad.

S. No	Description of item	QTY	Unit	Rate @ Unit	Amount (Rs.)
1	Dismantling the old flooring tiles and wall tiles in toilets, door frames, doors, toilet windows and granite platform in players dress room and dispose of the debris to outside of the ground. Including cost and conveyance of all materials and labour charges for dismantle etc., complete for finished item of work.	2,500.00	Sft		
2	Internal Plastering 20 mm thick in single coat in CM (1:5) prop. including scaffolding, cost and conveyance of material, labour charges and curing etc., comp.	1,800.00	Sft		
3	Plain cement concrete in (!:5:10) for foundations and under tile flooring using 40MM size hard machine crushed granite metal Including cost & conveyance of all materials ,curing & labour charges etc for finished item of work.	900.00	Sft		
	Net Amount				
	Add GST @ _____ %				
	Total Amount				

(Rupees in words _____ only)

Note:-

- The quoted price is inclusive of all materials, labour, equipment, tools & plants, scaffolding, transportation, insurance, taxes, duties, testing, finishing, and all incidental charges, with no extra claim whatsoever.
- Acceptance of any tender is subject to negotiations and HCA reserves it's right to negotiate with any tenderer including the lowest.

SIGNATURE OF APPLICANT

NAME: _____

DESIGNATION: _____

FIRM/COMPANY: _____

DATE: _____


(IMTIAZ KHAN)
Chief Executive Officer

